





# Plutonium Pit Production Analysis of Alternatives (AoA) Results & Next Steps

November 2017



NATIONAL NUCLEAR SECURITY ADMINISTRATION OFFICE OF DEFENSE PROGRAMS



## Pit Production Strategy and Progress

---

- To sustain plutonium infrastructure and establish capabilities to resume production of war reserve pits, NNSA is:
  - Investing over \$1B from FY19 – FY23 to sustain current operations and achieve 30 pits per year (ppy) production capability by 2026
  - Investing over \$2B in construction projects to replace CMR capabilities and reconfigure space to support production
  - Analyzing options, consistent with DOE O 413.3B, for long-term infrastructure needs to support the 80 ppy requirements and other mission needs
  
- Progress:
  - Safely resumed operations in PF-4 after a 3-year operational pause
  - Began construction activities for the first two CMRR subprojects:
    - RLUOB Equipment Installation Phase 2 (REI2)
    - PF-4 Equipment Installation Phase 1 (PEI1)
    - Both are on schedule and under budget
  - Fabricated two development pits in FY17; will build four development pits in FY18
  - Completed the Plutonium Pit Production Analysis of Alternatives in FY17



## Pit Production AoA Scope and Assumptions

---

- The AoA assessed alternatives to meet the sustained production capacity of no fewer than 80 ppy by 2030
  
- AoA Assumptions, Facts and Constraints
  - LANL is the Plutonium Center of Excellence for the enduring R&D mission
  - Capabilities installed under CMRR and Plutonium Sustainment remain in PF-4 and RLUOB
  - Operations in PF-4 to meet the 30 ppy goal in 2026 will continue and PF-4 will be capable of an estimated 30 ppy after the upgrades
  - The threshold requirement is 80 ppy at high confidence, due to pit aging estimates and planned production schedules to meet military requirements
  - Future pits will be produced using current processes and technology



## Evaluation Criteria and Other Considerations

---

### Evaluation Criteria:

- Cost, schedule, risk
- Ability to support objective requirements for NNSA and DOE missions
- Capacity for pit reuse operations simultaneous with pit remanufacturing
- Ability to accommodate surge capacity
- Synergy of plutonium science, metal preparation, and production
- Ability to accommodate future changes in mission requirements
- Useful lifetime

### Other Considerations:

- Qualified workforce & Expertise / Availability of workforce
- Design Agency (DA) and Production Agency (PA) Colocation / Resiliency
- Environmental
- Transportation
- Mission Impact



## AoA Results: Two Preferred Alternatives

---

1. Refurbishing and repurposing facilities at the Savannah River Site
  - Cost range: \$1.4-5.4 B
  - Schedule range: FY24-31
  - Risk: Reconfiguring a partially completed facility for a new mission in a new location
  
2. Additional footprint to accommodate pit production requirements at Los Alamos National Laboratory
  - Cost range: \$1.9-7.5 B
  - Schedule range: FY27-33
  - Risk: Less favorable cost and schedule for achieving a sustained 80 ppy facility



- Conduct detailed engineering analysis (EA) for both alternatives to inform the selection of a single alternative and support conceptual design
- The EA will analyze pre-conceptual design options at the two sites and provide an engineering feasibility report
- The results of the EA will inform conceptual design for the Deputy Secretary's approval of Critical Decision (CD)-1 (Approve Alternative Selection and Cost Range) in accordance with DOE Order 413.3B
  - Project baselines are not established until CD-2 approval (Approve Performance Baseline), which requires 90% design completion



**BACKUP**



DEFENSE PROGRAMS

# 41 Options Evaluated Resulting in Detailed Analysis of 5 Alternatives

| Production Approach                | Capabilities in PF-4                                    | Capabilities Outside PF-4            | 41 Alternatives Evaluated   |                                |                                   |                                   |
|------------------------------------|---|--------------------------------------|---|--------------------------------|-----------------------------------|-----------------------------------|
|                                    |   |                                      | 5 Options (shaded green) Received Detailed Cost, Schedule and Risk Analysis |                                |                                   |                                   |
| 0 - Status Quo                     | Pu Science and Cert + Metal Prep and 30 ppy             |                                      | LANLO   |                                |                                   |                                   |
| 1 - Split Production               | Pu Science and Cert + Metal Prep and 30 ppy             | Production 50 ppy at LANL            | LANL1-A (New)   | SRS1-B (K-Area)                | SRS1-C (WSB)                      | SRS1-D (New)                      |
|                                    |   | Production 50 ppy at SRS             | SRS1-A (MFFF)   | INL1-B (New)                   |                                   |                                   |
|                                    |   | Production 50 ppy at INL             | INL1-A (FPF)  | NNSS1 (New)                    |                                   |                                   |
|                                    | Pu Science and Cert + Metal Prep and other missions out | Production 50 ppy at Pantex/NNSS     | PX1 (New)   | LANL1-B (Aries and Pu238 stay) | LANL1-C (Aries stays, Pu238 goes) | LANL1-D (Aries goes, Pu238 stays) |
| 2 - Move Production and Metal Prep | Pu Science and Cert                                     | Metal Prep and 80 ppy at LANL        | LANL2 (New)   | SRS2-B (K-Area)                | SRS2-C (WSB)                      | SRS2-D (New)                      |
|                                    |   | Metal Prep and 80 ppy at SRS         | SRS2-A (MFFF)   | INL2-B (New)                   |                                   |                                   |
|                                    |   | Metal Prep and 80 ppy at INL         | INL2-A (FPF)  | NNSS2 (New)                    |                                   |                                   |
|                                    |   | Metal Prep and 80 ppy at Pantex/NNSS | PX2 (New)   |                                |                                   |                                   |
| 3 - Move Production                | Pu Science and Cert + Metal Prep                        | 80 ppy at LANL                       | LANL3 (New)   | SRS3-B (K-Area)                | SRS3-C (WSB)                      | SRS3-D (New)                      |
|                                    |   | 80 ppy at SRS                        | SRS3-A (MFFF)   | INL3-B (New)                   |                                   |                                   |
|                                    |   | 80 ppy at INL                        | INL3-A (FPF)  | NNSS3 (New)                    |                                   |                                   |
|                                    |   | 80 ppy at Pantex/NNSS                | PX3 (New)   |                                |                                   |                                   |
| 4 - Move Metal Prep                | Pu Science and Cert + 80 ppy                            | Metal Prep at LANL                   | LANL4 (New)   | SRS4-B (K-Area)                | SRS4-C (WSB)                      | SRS4-D (New)                      |
|                                    |   | Metal Prep at SRS                    | SRS4-A (MFFF)   | INL4-B (New)                   |                                   |                                   |
|                                    |   | Metal Prep at INL                    | INL4-A (FPF)  | NNSS4 (New)                    |                                   |                                   |
|                                    |   | Metal Prep at Pantex/NNSS            | PX4 (New)   |                                |                                   |                                   |

- 36 of 41 options were eliminated from further consideration after the team developed floor space estimates and initial cost, schedule, and risk assessments
  - Insufficient space
  - High cost for support facilities
  - Late to need
  - Facility condition
  - Mission disruption





# Summary of Results

| Approach                           | Refurbishment   |                                  | New Facility Construction      |           |           |
|------------------------------------|---|----------------------------------|--------------------------------|-----------|-----------|
| Alternative                        | SRS MFFF  | INL FPF                          | INL                            | SRS       | LANL      |
| CD-4 Cost Range (FY18\$B)          | 1.4 - 5.4   | 1.5 - 5.0                        | 1.9 - 6.9                      | 1.8 - 6.7 | 1.9 - 7.5 |
| CD-4 Schedule Range                | FY24 - 31   |                                  | FY27 - 33                      |           |           |
| 80 ppy Schedule Range              | FY29 - 36   |                                  | FY33 - 38                      |           |           |
| Risks                              | Potentially contentious state government                  |                                  |                                |           |           |
|                                    | No experience with pit production                         |                                  |                                |           |           |
|                                    | Delays in facility availability cause schedule delays     |                                  | [Redacted]                     |           |           |
|                                    | Potential structural issues with refurbishment            |                                  |                                |           |           |
|                                    | Change in safety basis from NRC to DOE                    |                                  |                                |           |           |
|                                    | Organizational Interface - Not an NNSA Site (DOE-NE site) |                                  |                                |           |           |
| Ample space for future flexibility |   | Experienced pit production techs |                                |           |           |
| Opportunities                      | Current NNSA production agency                            |                                  | Current NNSA production agency |           |           |
|                                    | NNSA Site Office  |                                  | NNSA Site Office               |           |           |